

Alder Creek Concrete & Flatwork

5620 W 86th St, Indianapolis, IN 46278
(317) 555-0142 · bids@aldercreekconcrete.com

Estimate

EST-2026-0214 · September 29, 2026

PREPARED FOR	JOB ADDRESS	ESTIMATE	
Tom & Rachel Adeyemi	Adeyemi residence — driveway replacement	Date	September 29, 2026
11482 Brookstone Dr, Fishers, IN 46038	11482 Brookstone Dr, Fishers, IN 46038	Valid until	October 29, 2026
(317) 555-0193	Driveway, street approach and front walk	Estimated start	Week of October 19
		Prepared by	Mike Duran, Owner

SLAB AREA	THICKNESS	MIX	REINFORCEMENT	FINISH
1,152 sq ft, 3 slabs	5" drive, 6" apron, 4" walk	4,000 PSI air-entrained	#4 rebar, 24" O.C. e.w.	Broom, tooled edges

SCOPE OF WORK — what you will remove and pour, and what "done" looks like

Remove the old driveway, approach and front walk; pour new reinforced, air-entrained slabs on a compacted stone base, broom finished, jointed and sealed.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
DEMO & SITE PREP		saw-cut, remove, haul, grade, base			
1	Break out old 4" driveway, approach and walk; haul 28 tons to recycler	1,152	SF	\$3.25	\$3,744.00
2	Saw-cut clean break lines at the public walk and curb	60	LF	\$5.50	\$330.00
3	Excavate for new base, fine grade and compact subgrade; haul spoils	1,152	SF	\$0.95	\$1,094.40
4	4" crushed-limestone base, placed and compacted	28	TON	\$58.00	\$1,624.00
5	Soft-subgrade repair allowance — undercut and replace with stone Billed per ton actually used, with photos	4	TON	\$85.00	\$340.00
FORMING & REINFORCEMENT		forms, rebar or mesh, isolation joints			
6	Set and strip edge forms, staked and pitched to drain	164	LF	\$3.50	\$574.00
7	#4 rebar at 24" on center each way, tied on chairs — drive and apron	1,151	LF	\$1.90	\$2,186.90
8	Isolation joint at garage slab, public walk, curb and porch	84	LF	\$2.50	\$210.00
POUR, FINISH & CURE		concrete, place and finish, joints, sealer, permit			
9	4,000 PSI air-entrained ready-mix: 17.9 CY in place + 8% waste	19.5	CY	\$245.00	\$4,777.50
10	Place, screed and broom finish; tooled edges; curing compound	1,152	SF	\$3.25	\$3,744.00
11	Control joints — saw-cut in drive and apron, tooled in the walk	156	LF	\$1.60	\$249.60
12	Penetrating silane-siloxane sealer, one coat after the 28-day cure	1,152	SF	\$0.55	\$633.60
13	Right-of-way permit and inspection for the approach — City of Fishers	1	LS	\$235.00	\$235.00
OPT.	OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL	ADD			
A	Side parking pad beside the garage, 10 × 20 ft, same 5" reinforced spec	\$2,780.00			
B	Replace the public-walk section across the driveway (5 × 20 ft) if the city inspector requires it	\$1,640.00			

TERMS — deposit, payment, subgrade allowance, exclusions, warranty

Deposit 30% on acceptance; balance due at completion. Subgrade repair beyond the 4-ton allowance billed at \$85/ton with photos, approved before we pour. If the city requires a thicker approach, extra concrete billed at \$245/CY. Cold-weather blankets, if needed, at cost. Excludes irrigation and landscape repair. 2-year workmanship warranty; hairline shrinkage cracks are normal and not covered.

Subtotal	\$19,743.00
Sales tax — included in material prices	\$0.00
Estimate total	\$19,743.00
Deposit due on acceptance (30%)	\$5,922.90
Balance due on completion	\$13,820.10

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Tom & Rachel Adeyemi

Estimated by · Alder Creek Concrete & Flatwork

SIGNATURE

SIGNATURE

Rachel Adeyemi

10/01/2026

Mike Duran, Owner

09/29/2026

PRINTED NAME

DATE

PRINTED NAME AND TITLE

DATE

Measured before removal. Subgrade repair beyond the allowance and owner changes are priced by written change order first. Call 811 before digging. Check your state's contract rules. Not legal advice.