

Prairie Line Drywall & Finishing

1406 NE Cornerstone Dr, Lee's Summit, MO 64086
(816) 555-0142 · estimates@prairielinedrywall.com

Estimate

EST-2026-0214 · September 24, 2026

PREPARED FOR	JOB ADDRESS	ESTIMATE	
Mark & Jenna Holloway	Holloway basement finish — drywall	Date	September 24, 2026
3317 SW Windsor Park Dr, Lee's Summit, MO 64082	3317 SW Windsor Park Dr, Lee's Summit, MO 64082	Valid until	October 24, 2026
(816) 555-0171	Family room, rec area, bedroom, bath and hall	Estimated start	Week of October 12
		Prepared by	Tom Ferris, Owner

BOARD AREA	BOARD TYPE	FINISH LEVEL	CEILING HEIGHT	TEXTURE
3,350 sq ft of board	½" regular, ceiling & MR	Level 4 (GA-214)	8 ft · soffits at 7 ft	Knockdown ceilings

SCOPE OF WORK — rooms, board, finish level and texture, and what "done" looks like

Hang and finish the basement family room, rec area, bedroom, bath and hall on framing by others: Level 4, knockdown ceilings, ready for primer.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
HANG		board by type, soffits, delivery and stocking			
1	Hang ½" regular board on walls, 4×12 sheets	1,856	SF	\$1.25	\$2,320.00
2	Hang ½" sag-resistant ceiling board, 4×12 sheets	996	SF	\$1.45	\$1,444.20
3	Hang ½" moisture-resistant board — bathroom walls and ceiling Tub alcove excluded; cement board by the tile setter	274	SF	\$1.75	\$479.50
4	Wrap duct soffits and beam, 3.5-ft girth	64	LF	\$10.50	\$672.00
5	Board delivery and hand-stocking to the basement Straight-run stair checked on the walkthrough: 12-ft sheets fit	1	LS	\$325.00	\$325.00
TAPE & FINISH		finish level, corner bead, window returns			
6	Tape, bed and finish all board to Level 4 — three coats, sanded	3,350	SF	\$1.05	\$3,517.50
7	Corner bead at outside corners, soffit edges and window returns	220	LF	\$2.75	\$605.00
8	Egress window returns — wrap three sides and sill, bead and finish	2	EA	\$185.00	\$370.00
TEXTURE, SPECIALTY & CLEANUP		texture, access panels, protection, haul-off			
9	Knockdown texture — ceilings and soffits	1,292	SF	\$0.65	\$839.80
10	Access panels, 14" × 14", supplied and installed (shower valve, main shutoff)	2	EA	\$110.00	\$220.00
11	Floor protection, daily cleanup and scrap haul-off	1	LS	\$450.00	\$450.00
OPT. OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL					ADD
A	Level 5 skim coat on the family room walls (640 SF), for a projector wall or raking light				\$640.00
B	Hang and finish the storage room walls and ceiling to Level 4 (about 560 SF of board)				\$1,395.00

TERMS — deposit, payment, inspections, exclusions, warranty

Deposit 30% on acceptance to schedule the crew and order board; balance due on completion after the walkthrough. Rough-in and insulation inspections (where required) must be signed off before we hang. Excludes framing fixes, blocking, painting and tile backer. Board added by owner changes is billed at the unit prices above. Workmanship warranty 1 year. Price firm through the valid-until date.

Subtotal	\$11,243.00
Sales tax — included in prices	\$0.00
Estimate total	\$11,243.00
Deposit due on acceptance (30%)	\$3,372.90
Balance due on completion	\$7,870.10

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Mark & Jenna Holloway

Estimated by · Prairie Line Drywall & Finishing

SIGNATURE

SIGNATURE

Jenna Holloway

09/26/2026

Tom Ferris, Owner

09/24/2026

PRINTED NAME

DATE

PRINTED NAME AND TITLE

DATE

Measured from the framing before board goes up. Owner changes and framing problems are priced by written change order first. Check your state's home-improvement contract rules. Not legal advice.