

PREPARED FOR	JOB ADDRESS	ESTIMATE
Marcus & Jenna Lindqvist	Lindqvist residence — basement finish	Date
6182 Brookhaven Dr, Columbus, OH 43229	6182 Brookhaven Dr, Columbus, OH 43229	Valid until
(614) 555-0173	1958 ranch · 100A overhead service	Estimated start
		Prepared by
		September 24, 2026
		October 24, 2026
		Week of October 12
		Ray Castillo, Owner

SERVICE	SCOPE	FINISHED AREA	NEW CIRCUITS	PERMIT / AHJ
100A to 200A, overhead	Service + basement finish	1,050 sq ft basement	12 circuits · 74 openings	City of Columbus

SCOPE OF WORK — service work, what you will wire, and what "done" looks like

Upgrade the overhead service from 100A to 200A with a new panel and grounding, then wire the basement finish: 12 new circuits, lights, bath fan and alarms.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
SERVICE & DISTRIBUTION		meter base, panel, grounding, changeover			
1	200A overhead service: new mast, weatherhead, meter base, entrance conductors	1	LS	\$2,150.00	\$2,150.00
2	200A main-breaker panel, 40-space; remove old panel, re-terminate 18 circuits	1	LS	\$2,380.00	\$2,380.00
3	Grounding and bonding: two ground rods, water and gas piping bonds	1	LS	\$395.00	\$395.00
4	Corrections to existing wiring found at changeover — allowance Billed at actual hours with photos; unused hours credited	4	HR	\$115.00	\$460.00
BRANCH CIRCUITS & DEVICES		home runs, receptacles, GFCIs, switches			
5	New branch circuits: breaker (AFCI/GFCI as required) and home run to panel	12	EA	\$250.00	\$3,000.00
6	Receptacle openings: tamper-resistant duplex, incl. box, cable and trim	22	EA	\$98.00	\$2,156.00
7	GFCI receptacle openings — bathroom, wet bar, storage room	4	EA	\$140.00	\$560.00
8	Switch openings: single-pole, 3-way and dimmer	15	EA	\$85.00	\$1,275.00
LIGHTING, TESTING & PERMITS		fixtures, fans, alarms, permit, inspections			
9	6" LED recessed wafer lights, contractor-supplied, incl. cable	24	EA	\$86.00	\$2,064.00
10	Hang owner-supplied fixtures: vanity, three bar pendants, storage light	5	EA	\$102.00	\$510.00
11	Bath exhaust fan, ducted to exterior	1	EA	\$465.00	\$465.00
12	Hardwired smoke/CO combination alarms, interconnected	3	EA	\$130.00	\$390.00
13	Permit, rough-in and final inspections — City of Columbus; test and label panel	1	LS	\$385.00	\$385.00
OPT.	OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL				ADD
A	Low-voltage: four Cat6 data and two coax drops home-run to a media panel				\$1,180.00
B	50A 240V circuit and NEMA 14-50 receptacle in the garage for an EV charger (after load calculation)				\$1,240.00

TERMS — deposit, payment, wiring allowance, fixtures, exclusions, warranty	Subtotal	\$16,190.00
Deposit 30% on acceptance to order the panel and service equipment; balance due when the final inspection passes. Existing-wiring corrections beyond the 4-hour allowance billed at \$115/hr with photos. Owner supplies decorative fixtures. Excludes framing, drywall, patching, painting and utility-side work or fees. Workmanship warranty 2 years; manufacturer warranties pass through.	Sales tax — included in prices	\$0.00
	Estimate total	\$16,190.00
	Deposit due on acceptance (30%)	\$4,857.00
	Balance due on completion	\$11,333.00

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Marcus & Jenna Lindqvist

Estimated by · Tallwood Electric Co.

SIGNATURE	SIGNATURE
Jenna Lindqvist	Ray Castillo, Owner
09/26/2026	09/24/2026
PRINTED NAME	PRINTED NAME AND TITLE
DATE	DATE