

PREPARED FOR	JOB ADDRESS	ESTIMATE
Tom & Angela Reyes 1186 Coral Mesa Ave, Henderson, NV 89074 (702) 555-0163	Reyes residence — new floors 1186 Coral Mesa Ave, Henderson, NV 89074 Single-story home on slab · 3 bed / 2 bath	Date September 24, 2026 Valid until October 24, 2026 Estimated start Week of October 12 Prepared by Dana Whitaker, Owner

FLOOR AREA	FLOORING	ROOMS	SUBFLOOR	REMOVAL
1,189 sq ft measured	20-mil LVP + porcelain tile	Living areas, 3 BR, 1 bath	Concrete slab	Carpet + ceramic tile

SCOPE OF WORK — what comes out, what goes down in which rooms, and what "done" looks like

Remove carpet and ceramic tile, level low spots in the slab, and install rigid-core luxury vinyl plank in the living areas and bedrooms and porcelain tile in the primary bath, with new quarter round.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
REMOVAL & PREP					tear-out, disposal, floor leveling
1	Remove carpet, pad and tack strip — living, hall, bedrooms; haul away	857	SF	\$0.75	\$642.75
2	Remove ceramic tile — kitchen, dining, primary bath; grind thinset	332	SF	\$3.50	\$1,162.00
3	Slab leveling — prime and pour self-leveler at low spots — allowance Billed per bag actually used, with photos	6	BAG	\$95.00	\$570.00
INSTALLATION					flooring, underlayment, setting materials, labor
4	Luxury vinyl plank, 20-mil, rigid core — 23.64 sq ft/box, incl. 10% waste	53	BOX	\$82.50	\$4,372.50
5	Underlayment, 2 mm with attached vapor barrier — 100 sq ft rolls	12	RL	\$46.00	\$552.00
6	Install LVP floating floor over underlayment; undercut door jams	1,129	SF	\$2.40	\$2,709.60
7	Porcelain tile, 12" × 24" matte — 15.5 sq ft/box, incl. 15% waste	5	BOX	\$65.00	\$325.00
8	Setting materials — modified thinset, grout, grout sealer	1	LS	\$135.00	\$135.00
9	Install tile on slab, 1/3 offset, 1/8" joints; grout and seal	60	SF	\$12.50	\$750.00
TRIM, TRANSITIONS & OTHER					quarter round, baseboard, transitions, toilet reset
10	Quarter round, primed MDF, installed; nail holes filled, ready for paint	330	LF	\$2.75	\$907.50
11	Transitions — T-molding, reducers and end caps to match the LVP	4	EA	\$55.00	\$220.00
12	Pull and reset toilet — new wax ring and supply line	1	EA	\$195.00	\$195.00
OPT.	OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL				ADD
A	New 5¼" primed MDF baseboard in place of the quarter round, 330 LF (net add)				\$825.00
B	Hall bath floor in the same porcelain tile, 38 sq ft, incl. tear-out and toilet reset				\$1,095.00

TERMS — deposit, payment, leveling allowance, exclusions, warranty

Deposit 40% on acceptance to order material; balance due at completion after the final walkthrough. Leveling beyond the 6-bag allowance is billed at \$95/bag with photos. Owner clears furniture; we move the range and refrigerator. Excludes painting, plumbing and slab-crack repair. Workmanship warranty 2 years; the manufacturer’s warranty passes through. Leftover boxes stay with the owner.

Subtotal	\$12,541.35
Sales tax — included in prices	\$0.00
Estimate total	\$12,541.35
Deposit due on acceptance (40%)	\$5,016.54
Balance due on completion	\$7,524.81

Acceptance
By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Tom & Angela Reyes

Estimated by · Sloan Canyon Floor Co.

SIGNATURE	SIGNATURE
Angela Reyes	Dana Whitaker, Owner
09/26/2026	09/24/2026
PRINTED NAME	PRINTED NAME AND TITLE
DATE	DATE

Based on measurements taken before tear-out. Subfloor damage, moisture and owner changes are priced by written change order first. Check your state’s contract rules. Not legal advice.