

Kestrel Ridge Landscape & Irrigation

1925 Blue Spruce Dr, Fort Collins, CO 80524
(970) 555-0162 · bids@kestrelridgelandscap.com

Estimate

EST-2026-0214 · September 25, 2026

PREPARED FOR	JOB ADDRESS	ESTIMATE	
Elena & Mark Soriano	Soriano residence — front yard	Date	September 25, 2026
2741 Sandstone Ct, Fort Collins, CO 80526	2741 Sandstone Ct, Fort Collins, CO 80526	Valid until	October 25, 2026
(970) 555-0119	Clay soil · existing 4-zone sprinkler system	Estimated start	Week of October 5
		Prepared by	Mateo Vargas, Owner

LAWN / BEDS	SOIL PREP	BED MULCH	IRRIGATION	PLANT WARRANTY
992 / 922 sq ft	1 in. compost, tilled 6 in.	3 in. shredded cedar	2 drip zones, 2 spray adjusted	1 year, plants & tree

SCOPE OF WORK — what you will remove and install, and what "done" looks like

Remove the front lawn and the overgrown rock bed, amend the clay soil, and install new sod, three planting beds on drip irrigation, steel edging and cedar mulch.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
SITE PREP & GRADING		turf removal, clean-out, soil prep, grade			
1	Strip existing turf with a sod cutter; haul off and dispose	1,546	SF	\$0.95	\$1,468.70
2	Clean out foundation bed: 6 junipers, rock mulch and fabric; haul off	1	LS	\$1,380.00	\$1,380.00
3	Soil prep: 1 in. compost (6.5 CY) tilled 6 in.; fine grade to drain	1,914	SF	\$0.80	\$1,531.20
4	Garden soil blend, 2 in. over beds; crown the corner bed	6.5	CY	\$112.00	\$728.00
PLANTING, SOD & MULCH		sod, trees, shrubs, perennials, mulch			
5	Kentucky bluegrass sod, rolled and watered in Priced on the measured lawn; cutting waste is in the price	992	SF	\$1.60	\$1,587.20
6	Ornamental crabapple, 1.5 in. caliper B&B, staked	1	EA	\$465.00	\$465.00
7	Shrubs, 5-gal — rabbitbrush, fernbush, blue mist spirea	12	EA	\$85.00	\$1,020.00
8	Perennials and grasses, 1-gal — little bluestem, catmint, penstemon	60	EA	\$27.00	\$1,620.00
9	Shredded cedar mulch, 3 in. deep in all beds	9.5	CY	\$92.00	\$874.00
IRRIGATION, EDGING & CLEANUP		drip, spray heads, edging, final cleanup			
10	Convert 2 bed zones to drip: filter, regulator, tubing, 88 emitters	2	ZN	\$640.00	\$1,280.00
11	Relocate or add lawn spray heads for head-to-head coverage; new nozzles	7	EA	\$78.00	\$546.00
12	Steel edging, 1/8 × 4 in., staked — every lawn-to-bed edge	142	LF	\$8.50	\$1,207.00
13	Final cleanup, walkthrough and a written watering schedule	1	LS	\$245.00	\$245.00
OPT.	OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL				ADD
A	Replace the cracked concrete entry walk with a 4 × 32 ft paver walk on 6 in. compacted base				\$4,380.00
B	Weather-based Wi-Fi irrigation controller, installed and programmed				\$465.00

TERMS — deposit, payment, sprinkler repairs, exclusions, plant warranty

Deposit 40% on acceptance to order plants and sod; balance due at completion after the walkthrough. Sprinkler repairs beyond this scope billed at \$85/hr plus parts, approved first. We call 811; owner marks private lines. Excludes hardscape. Plants and tree warranted 1 year with drip running; sod not warranted once installed. Price firm through the valid-until date.

Subtotal	\$13,952.10
Sales tax — included in prices	\$0.00
Estimate total	\$13,952.10
Deposit due on acceptance (40%)	\$5,580.84
Balance due on completion	\$8,371.26

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Elena & Mark Soriano

Estimated by · Kestrel Ridge Landscape & Irrigation

SIGNATURE

SIGNATURE

Elena Soriano

09/28/2026

Mateo Vargas, Owner

09/25/2026

PRINTED NAME

DATE

PRINTED NAME AND TITLE

DATE

Based on site measurements. Buried debris, rock and broken sprinkler lines are priced by written change order first. Check your state's contract and deposit rules. Not legal advice.