

|                                                                                   |                                                                                                                              |                                                                                                                                             |
|-----------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|
| PREPARED FOR                                                                      | JOB ADDRESS                                                                                                                  | ESTIMATE                                                                                                                                    |
| Priya & Daniel Mercer<br>2917 Linden Glen Ct, Henrico, VA 23233<br>(804) 555-0187 | Mercer residence — interior repaint<br>2917 Linden Glen Ct, Henrico, VA 23233<br>Occupied two-story, built 1998 · main floor | Date<br>Valid until<br>Estimated start<br>Prepared by<br>September 24, 2026<br>October 24, 2026<br>Week of October 12<br>Dana Hollis, Owner |

|                |                              |                               |                            |                            |
|----------------|------------------------------|-------------------------------|----------------------------|----------------------------|
| PAINTABLE AREA | SURFACES                     | COATS                         | PAINT & SHEEN              | COLORS                     |
| 3,424 sq ft    | Walls, ceilings, trim, doors | Walls 2 · ceilings 1 · trim 2 | Premium acrylic · eggshell | 3 wall colors · white trim |

SCOPE OF WORK — rooms and surfaces you will paint, the prep included, and what "done" looks like

Repaint the main floor: living, dining and family rooms, two-story foyer, front hall and powder room. Walls, ceilings, baseboard, 7 doors and 10 window casings, with furniture moved and covered.

| #                   | DESCRIPTION                                                                                                                  | QTY   | UNIT | UNIT PRICE | AMOUNT                                       |
|---------------------|------------------------------------------------------------------------------------------------------------------------------|-------|------|------------|----------------------------------------------|
| PREP & PROTECTION   |                                                                                                                              |       |      |            | cover, mask, patch, caulk, spot-prime        |
| 1                   | Move and cover furniture, mask floors and fixtures; daily cleanup                                                            | 6     | RM   | \$100.00   | \$600.00                                     |
| 2                   | Wall prep: fill nail holes and hairline cracks, sand, spot-prime                                                             | 2,547 | SF   | \$0.25     | \$636.75                                     |
| 3                   | Caulk baseboard and casing joints; fill and sand trim                                                                        | 251   | LF   | \$1.15     | \$288.65                                     |
| 4                   | Drywall repair allowance — cracks and dents beyond normal patching<br>Billed at \$75/hr for hours actually used, with photos | 4     | HR   | \$75.00    | \$300.00                                     |
| WALLS & CEILINGS    |                                                                                                                              |       |      |            | coats and sheen by surface, high-wall access |
| 5                   | Walls — two coats premium acrylic, eggshell (three colors)                                                                   | 2,547 | SF   | \$1.45     | \$3,693.15                                   |
| 6                   | Ceilings — one coat flat ceiling white                                                                                       | 877   | SF   | \$0.90     | \$789.30                                     |
| 7                   | Two-story foyer — plank and ladder setup for 18-ft walls and ceiling                                                         | 1     | LS   | \$360.00   | \$360.00                                     |
| TRIM, DOORS & OTHER |                                                                                                                              |       |      |            | baseboard, doors, windows, touch-up          |
| 8                   | Baseboard — two coats semi-gloss enamel                                                                                      | 251   | LF   | \$2.50     | \$627.50                                     |
| 9                   | Interior doors — slab, jamb and casing, both sides, two coats semi-gloss                                                     | 7     | EA   | \$140.00   | \$980.00                                     |
| 10                  | Window casing, sill and apron — two coats semi-gloss                                                                         | 10    | EA   | \$70.00    | \$700.00                                     |
| 11                  | Final walkthrough and touch-up; remove masking; leave labeled leftover paint                                                 | 1     | LS   | \$150.00   | \$150.00                                     |
| OPT.                | OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL                                                                |       |      |            | ADD                                          |
| A                   | Stair handrail and 24 balusters — sand, spot-prime and two coats semi-gloss                                                  |       |      |            | \$985.00                                     |
| B                   | Crown molding in the living and dining rooms, 110 LF — caulk and two coats semi-gloss                                        |       |      |            | \$495.00                                     |

|                                                                                                                                                                                                                                                                                                                                                                                                                            |                                 |            |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|------------|
| TERMS — deposit, payment, drywall allowance, color changes, exclusions, warranty                                                                                                                                                                                                                                                                                                                                           | Subtotal                        | \$9,125.35 |
| Deposit 25% on acceptance to book the crew and buy paint; balance due at completion after the final walkthrough. Includes 4 hours of drywall repair; more is billed at \$75/hr with photos. Colors are final before we start: a color change after paint goes on, or a deep color needing a third coat, is priced by change order. Excludes kitchen, closet interiors and wallpaper removal. Workmanship warranty 2 years. | Sales tax — included in prices  | \$0.00     |
|                                                                                                                                                                                                                                                                                                                                                                                                                            | Estimate total                  | \$9,125.35 |
|                                                                                                                                                                                                                                                                                                                                                                                                                            | Deposit due on acceptance (25%) | \$2,281.34 |
|                                                                                                                                                                                                                                                                                                                                                                                                                            | Balance due on completion       | \$6,844.01 |

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Priya & Daniel Mercer

Estimated by · Hollis & Reed Painting Co.

|              |                        |
|--------------|------------------------|
| SIGNATURE    | SIGNATURE              |
| Priya Mercer | Dana Hollis, Owner     |
| 09/26/2026   | 09/24/2026             |
| PRINTED NAME | PRINTED NAME AND TITLE |
|              | DATE                   |

Measured on a walkthrough before work. Hidden damage, color changes after paint is applied and added work are priced by written change order first. Homes built before 1978 may require lead-safe (EPA RRP) work practices. Check your state's contract and deposit rules. Not legal advice.