

PREPARED FOR	JOB ADDRESS	ESTIMATE
Tom & Alicia Brennan	Brennan residence — primary bath	DateSeptember 25, 2026
418 Birchwood Ln, Westerville, OH 43081	418 Birchwood Ln, Westerville, OH 43081	Valid untilOctober 25, 2026
(614) 555-0193	1968 two-story · water heater in basement	Estimated startRough-in week of Oct 19
		Prepared byBen Alder, Owner

FIXTURES	SUPPLY PIPE	DRAIN & VENT	WATER HEATER	PERMIT
5 fixtures + water heater	PEX-A, 3/4" and 1/2"	PVC DWV to cast-iron stack	50-gal gas, atmospheric	Included · rough + final

SCOPE OF WORK — fixtures and systems you will rough in, trim or replace, and what "done" looks like

Rough in and trim the new primary bath (toilet, double vanity, walk-in shower, freestanding tub) and replace the gas water heater.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
ROUGH-IN (SUPPLY & DWV)		demo, drains, vents, supply, valve bodies			
1	Disconnect and cap fixtures; remove galvanized supply and old drains	1	LS	\$450.00	\$450.00
2	Rough-in, water closet — relocated 3" drain, vent, flange, cold supply	1	EA	\$750.00	\$750.00
3	Rough-in, lavatories — 1-1/2" drains and vents, hot and cold stub-outs	2	EA	\$605.00	\$1,210.00
4	Rough-in, walk-in shower — pressure-balance valve body, 2" drain, vent	1	EA	\$1,120.00	\$1,120.00
5	Rough-in, freestanding tub — floor-mount filler valve, drain, vent	1	EA	\$1,420.00	\$1,420.00
FIXTURES & TRIM		fixture allowance, set and trim each fixture			
6	Fixture and faucet allowance — toilet, 2 lav faucets, shower trim, tub filler	1	AL	\$2,400.00	\$2,400.00
7	Set water closet — seal, bolts, quarter-turn stop, braided supply	1	EA	\$235.00	\$235.00
8	Trim lavatories — faucets, drains, P-traps, stops and supplies	2	EA	\$280.00	\$560.00
9	Trim shower — valve trim, arm and head; flush and leak-check	1	EA	\$130.00	\$130.00
10	Set owner-supplied freestanding tub, connect drain, install filler trim	1	EA	\$325.00	\$325.00
WATER HEATER, TESTING & PERMITS		heater, expansion tank, tests, inspections, permit			
11	Replace 50-gal gas water heater, atmospheric vent — like for like Haul-away, gas connector, sediment trap, T&P discharge line and pan	1	EA	\$2,225.00	\$2,225.00
12	Thermal expansion tank on the cold inlet, charged to house pressure	1	EA	\$195.00	\$195.00
13	Supply and DWV tests, rough and final inspections, permits at cost	1	LS	\$545.00	\$545.00
OPT.	OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL	ADD			
A	Hot-water recirculation pump at the heater with a thermostatic crossover valve at the vanity	\$685.00			
B	Replace the remaining galvanized supply to the kitchen, laundry and hall bath with PEX-A	\$3,280.00			

TERMS — deposit, payment, fixture allowance, exclusions, warranty

Deposit 30% on acceptance; balance at completion after final inspection. Fixture allowance \$2,400: selections over or under it adjust the total at our cost. Owner supplies the tub, vanity and tops. Excludes finish demo, framing, drywall, tile and patching, and vent or gas-line changes beyond the heater hookup. Workmanship warranty 1 year; manufacturer warranties pass through.

Subtotal	\$11,565.00
Sales tax — included in prices	\$0.00
Estimate total	\$11,565.00
Deposit due on acceptance (30%)	\$3,469.50
Balance due on completion	\$8,095.50

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Tom & Alicia Brennan

Estimated by · Alder & Stone Plumbing

SIGNATURE	SIGNATURE
Alicia Brennan	Ben Alder, Owner
09/28/2026	09/25/2026
PRINTED NAME	DATE
DATE	PRINTED NAME AND TITLE

Based on a walkthrough before demolition. Hidden conditions and owner changes are priced by written change order first. Work is permitted and inspected under the local plumbing code. Not legal advice.