

PREPARED FOR	JOB ADDRESS	ESTIMATE
Marcus & Elena Brandt	Brandt residence — furnace & AC replacement	Date
5412 Hollow Oak Dr, Westerville, OH 43081	5412 Hollow Oak Dr, Westerville, OH 43081	Valid until
(614) 555-0142	Ranch with finished basement · equipment in basement	Estimated start
		Prepared by
		September 25, 2026
		October 25, 2026
		Week of October 5
		Luis Romero, Owner

SYSTEM TYPE	CAPACITY	EFFICIENCY	HOME / ZONES	THERMOSTAT
Split AC + gas furnace	3 ton · 60,000 BTU	15.2 SEER2 · 96% AFUE	2,050 sq ft · 1 zone	Wi-Fi programmable

SCOPE OF WORK — what you will remove and install, how it was sized, and what "done" looks like

Replace the 100,000 BTU furnace, AC and coil with a matched system sized by Manual J load calculation (attached); add two supply runs and a bedroom return.

#	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
EQUIPMENT		outdoor unit, furnace or air handler, coil			
1	3-ton split air conditioner, 15.2 SEER2, R-454B; new pad, disconnect and whip	1	EA	\$4,150.00	\$4,150.00
2	60,000 BTU 96% AFUE two-stage gas furnace, variable-speed blower	1	EA	\$3,495.00	\$3,495.00
3	Matched 3-ton cased evaporator coil (AHRI-rated combination)	1	EA	\$1,210.00	\$1,210.00
INSTALLATION & DUCTWORK		removal, sheet metal, line set, refrigerant, venting, duct			
4	Remove and dispose of old furnace, AC and coil; recover refrigerant	1	LS	\$450.00	\$450.00
5	New supply plenum, return drop and 4" media filter cabinet, sealed with mastic	1	LS	\$1,180.00	\$1,180.00
6	New line set, 3/8" × 3/4" insulated copper; pressure test and evacuate	35	LF	\$17.50	\$612.50
7	Added refrigerant charge beyond the factory charge, weighed in	0.75	LB	\$78.00	\$58.50
8	2" PVC intake and exhaust, sidewall termination; 18 LF condensate drain	1	LS	\$780.00	\$780.00
9	Add 6" insulated supply runs to the basement office, with boots and registers	2	EA	\$345.00	\$690.00
10	Add 14" return from the primary bedroom, with grille Existing return undersized: static measured at 0.86 in. w.c.	1	EA	\$565.00	\$565.00
CONTROLS, STARTUP & PERMITS		thermostat, startup and commissioning, permit			
11	Wi-Fi programmable thermostat with new 18/8 wire (80 LF)	1	EA	\$335.00	\$335.00
12	Startup and commissioning: charge, static, temperature split, gas pressure	1	LS	\$295.00	\$295.00
13	Mechanical permit and inspection	1	LS	\$195.00	\$195.00
OPT.	OPTIONAL ITEMS — PRICED SEPARATELY, NOT INCLUDED IN THE TOTAL				ADD
A	Dual fuel: 3-ton heat pump in place of the AC, 15.2 SEER2 / 7.8 HSPF2				\$1,850.00
B	Chimney liner for the water heater, if the venting check after furnace removal requires one				\$1,150.00

TERMS — deposit, payment, refrigerant, exclusions, warranty	Subtotal	\$14,016.00
Deposit 40% on acceptance to order equipment; balance due at completion after startup and walkthrough. Refrigerant beyond the estimated 0.75 lb billed at \$78/lb, weighed and recorded. Excludes electrical panel or circuit changes, asbestos testing or removal, and drywall repair. 2-year labor warranty; the manufacturer's parts warranty passes through, and we register it for you.	Sales tax — included in prices	\$0.00
	Estimate total	\$14,016.00
	Deposit due on acceptance (40%)	\$5,606.40
	Balance due on completion	\$8,409.60

Acceptance

By signing, the customer accepts this estimate, the optional items marked above and these terms.

Accepted by · Marcus & Elena Brandt

Estimated by · Kestrel Heating & Air

SIGNATURE	SIGNATURE
Elena Brandt	Luis Romero, Owner
09/27/2026	09/25/2026
PRINTED NAME	PRINTED NAME AND TITLE
DATE	DATE